

**SECTION 00 91 13**

**ADDENDUM NO. 2**

**March 13, 2025**

**PROJECT:** Warwick Public Schools Bid No. 25-0016

Exterior Door Upgrades  
Cedar Hill Elementary School  
35 Red Chimney Drive, Warwick, Rhode Island 02886  
and  
Park Elementary School  
40 Asylum Road, Warwick, Rhode Island 02886

- This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 25, 2025 as noted below.
- Please advise all sub-contractors.
- Acknowledge receipt of this Addendum in the space provided on the Bid Form.

**DRAWINGS**

A. ITEM NO. 1 – DRAWING A2.0-D (Cedar Hill Elementary School)

1. New weatherstripping as described in the Specifications are to be installed around the perimeter of all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
2. A new threshold is to be installed at all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.  
The only doors excluded are doors B5, C15, A22, and A20.
3. New astragal weatherstripping is to be installed at all existing and new pairs of doors listed in the Exterior Door & Frame Schedule between the two doors. Removable and permanent metal astragals are not included in this project. Where they currently exist, they are to be removed, disposed and new, wider doors installed and new weatherstripping installed between the doors.

B. ITEM NO. 2 – DRAWING A2.0-E (Park Elementary School)

1. New weatherstripping as described in the Specifications are to be installed around the perimeter of all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
2. A new threshold is to be installed at all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.  
The only doors excluded are doors C11, C12, B9, A6, B8, A4, B14, A25, and A20.

3. New astragal weatherstripping is to be installed at all existing and new pairs of doors listed in the Exterior Door & Frame Schedule between the two doors. Removable and permanent metal astragals are not included in this project. Where they currently exist, they are to be removed, disposed and new, wider doors installed and new weatherstripping installed between the doors.

End of Addendum No. 2