

SECTION 00 91 13

ADDENDUM NO. 2

March 13, 2025

PROJECT: Warwick Public Schools Bid No. 25-0015

Exterior Door Upgrades
Hoxsie Elementary School
and
Robertson Elementary School
and
E.T. Wyman Elementary School

- This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 25, 2025 as noted below.
- Please advise all sub-contractors.
- Acknowledge receipt of this Addendum in the space provided on the Bid Form.

DRAWINGS

A. ITEM NO. 1 – DRAWING A2.0-A (Hoxsie Elementary School)

1. New weatherstripping as described in the Specifications are to be installed around the perimeter of all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
2. A new threshold is to be installed at all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
The only doors excluded are doors B9, D10, C15, D17, D13, A19, B18, and D16.
3. New astragal weatherstripping is to be installed at all existing and new pairs of doors listed in the Exterior Door & Frame Schedule between the two doors. Removable and permanent metal astragals are not included in this project. Where they currently exist, they are to be removed, disposed and new, wider doors installed and new weatherstripping installed between the doors.

B. ITEM NO. 2 – DRAWING A2.0-B (Robertson Elementary School)

1. New weatherstripping as described in the Specifications are to be installed around the perimeter of all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
2. A new threshold is to be installed at all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing.
The only doors excluded are doors C11, B14, D19, A20, 22 and 23.

3. New astragal weatherstripping is to be installed at all existing and new pairs of doors listed in the Exterior Door & Frame Schedule between the two doors. Removable and permanent metal astragals are not included in this project. Where they currently exist, they are to be removed, disposed and new, wider doors installed and new weatherstripping installed between the doors.

C. ITEM NO. 3 – DRAWING A2.0-C (E.T. Wyman Elementary School)

1. New weatherstripping as described in the Specifications are to be installed around the perimeter of all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing. The only doors excluded are doors A1B1 and A1B2.
2. A new threshold is to be installed at all existing and new doors listed in the Exterior Door & Frame Schedule shown on this drawing. The only doors excluded are doors D9, D10, A1B1, A1B2, and B11.
3. New astragal weatherstripping is to be installed at all existing and new pairs of doors listed in the Exterior Door & Frame Schedule between the two doors. Removable and permanent metal astragals are not included in this project. Where they currently exist, they are to be removed, disposed and new, wider doors installed and new weatherstripping installed between the doors.

End of Addendum No. 2